



Shafley Municipal Drain

December 18, 2025

Prepared for:



Headway Engineering
23-500 Fairway Road South
Suite 308
Kitchener, Ontario N2C 1X3
226 243 6614
www.headwayeng.ca

Kitchener, Ontario

December 18, 2025

To the Mayor and Members of Council:

**Re: Shafley Municipal Drain
Township of Wainfleet
Our Reference No. WNFLT-002**

Headway Engineering is pleased to provide its report for the **Shafley Municipal Drain** in the Township of Wainfleet.

The preparation of this report was authorized by a resolution of the Council of the Township of Wainfleet on September 10, 2019, and July 13, 2021 per Section 78 of the Drainage Act.

The primary objective of this report is to improve the Shafley Municipal Drain by increasing depth for tile drainage where practical, replace existing access culverts and extending culverts where needed for road safety.

A summary of the assessments for this project are as follows:

Municipal Lands	\$299,302
Privately Owned Non-Agricultural	\$ 63,527
Privately Owned Agricultural	\$263,771
Total Estimated Assessments	\$626,600

Yours truly,

Stephen Brickman, P.Eng.
Project Engineer and Manager



Adam Hall
Project Coordinator
HEADWAY ENGINEERING

SB/





CONTENTS

1.0	INTRODUCTION AND LOCATION	1
2.0	AUTHORIZATION.....	1
3.0	DRAINAGE HISTORY	1
4.0	MEETINGS AND PUBLIC ENGAGEMENTS	1
5.0	FINDINGS.....	2
6.0	DESIGN CONSIDERATIONS.....	4
7.0	ENVIRONMENTAL CONSIDERATIONS	5
8.0	RECOMMENDATIONS.....	5
9.0	SUMMARY OF PROPOSED WORKS.....	6
10.0	WORKING AREA AND ACCESS.....	6
11.0	SCHEDULES	7
12.0	ALLOWANCES	7
13.0	ESTIMATED CONSTRUCTION COSTS	8
14.0	SUMMARY OF ESTIMATED PROJECT COSTS.....	8
15.0	ASSESSMENT	9
16.0	GRANT ELIGIBILITY	10
17.0	ABANDONMENT OF EXISTING MUNICIPAL DRAINS	10
18.0	MAINTENANCE	11

SCHEDULES

SCHEDULE A - ALLOWANCES

SCHEDULE B - ESTIMATED CONSTRUCTION COSTS

SCHEDULE C - ASSESSMENT FOR ESTIMATED CONSTRUCTION

SCHEDULE D - ASSESSMENT FOR FUTURE MAINTENANCE

SPECIFICATIONS FOR THE CONSTRUCTION OF MUNICIPAL DRAINAGE WORKS

1.0 INTRODUCTION AND LOCATION

The Council of the Township of Wainfleet has appointed Headway Engineering to investigate a request for improvements to the Shafley Municipal Drain.

The project services parts of Lots 35 and 36, Concessions 5, parts of Lots 34 to 38, Concession 6, and parts of Lot 36, Concession 7 in the Township of Wainfleet, Niagara Region.

The drainage area is approximately 276.7 hectares. Land use within the watershed is predominantly agricultural, with smaller portions consisting of woodlots, roads, and residential properties.

The attached Plans, Profiles, and Details; Drawing Numbers 1 to 7, and Specifications form part of this report. They show and describe in detail the location and extent of the work to be completed and the lands and roads which are affected.

2.0 AUTHORIZATION

Authority to prepare a report was first obtained by a resolution of the Township of Wainfleet Council at its September 10, 2019, meeting to appoint Dietrich Engineering Limited to prepare an Engineer's Report under Section 78 of the Drainage Act.

Authority to prepare this report was granted by a resolution of the Township of Wainfleet Council on July 13, 2021. At that meeting, Council transitioned its appointment of the Engineer to Headway Engineering in accordance with Section 8(2) of the Drainage Act

3.0 DRAINAGE HISTORY

The historical records for the Shafley Municipal Drain include two engineering reports. The latest report completed by J. R. Spriet, P. Eng, prepared in 1989, mentions the last reconstruction of the Shafley Drain prior to the 1989 report was completed by C. J. Clarke, P. Eng. in 1961. No records are available for the report authorizing the original construction of the Shafley Drain.

The table below summarizes all documented drainage reports.

Date	Report Author	Notes (Based on Available Records)
December 1961	C.J. Clarke, P. Eng.	The 1961 report provided for the reconstruction of the open drain.
April 1989	J. R. Spriet, P. Eng	The 1989 report references excavation of approximately 1,836m of the open drain, the construction of three closed tile drainage systems, Branch 'A', 'B' and 'C' and the installation of a pump station on Branch 'A'

Table 1 - Summary of Engineering Reports

4.0 MEETINGS AND PUBLIC ENGAGEMENTS

A series of technical, stakeholder, and statutory meetings have been held throughout the development of this report. These engagements involved landowners, municipal staff, regulatory authorities, and



railway representatives. The meetings occurred as design options were refined and new information became available. The key meetings are summarized in Table 2.

Meeting Date	Meeting Description	Summary
November 20, 2019	On-Site Meeting (Section 9(1) of the Drainage Act)	Preliminary plan circulated; meeting held to investigate the request for improvements.
October 19, 2022	Stakeholders Meeting 1	Review of options and alignments for the proposed drainage systems, including preliminary design considerations and associated cost distributions.
June 28, 2023	Canadian Pacific Railway	Meeting held to review the proposed design, the required rail crossings, and associated costs. Early coordination involved confirming whether CP or CN was the responsible authority; CP ultimately confirmed jurisdiction. CP claimed that they would not participate financially. The meeting concluded with CP's position noted and the process moved forward through later stakeholder discussions.
November 3, 2023	Stakeholders Meeting 2	The project status and possible next steps were reviewed. Pump options had been discussed previously, and at this meeting the proponent and Township confirmed that this was the direction to pursue.
January 9, 2025	Stakeholders Meeting 3	The meeting provided a review of options and alignments for Branch 'A' of the Shafley Drain. Headway Engineering presented the option to drain subsurface water to the Collver Drain.
July 9, 2025	Public Information Meeting	The meeting provided a review of the proposed design, estimated costs, and the proposed assessments, among other information. All meeting materials were posted online following the meeting, and all parties invited to attend the meeting were provided with access instructions to the meeting materials.
July 22, 2025	Stakeholder Meeting 4	Meeting held with several landowners and the Drainage Superintendent to review road safety concerns near the lower end of the Shafley Drain.
November 7, 2025	Department of Fisheries and Oceans (DFO)	Headway Engineering met with DFO to review the proposed works and discuss how the project complies with the Fisheries Act and the Species at Risk Act. The proposal was presented and explained.

Table 2 – Summary of Meetings and Engagements.

5.0 FINDINGS

Based on the information collected during field investigations, surveys, public engagements, and review of documentation, the following summarizes Headway Engineering's findings:

5.1 Watershed Condition (Hydrology):

- The watershed was established through the analysis of tile drainage maps, previous engineers' reports for the Shafley Drain and surrounding drainage systems, field



investigations, surveys and data analysis of the LiDAR derived digital data from Land Information Ontario. The drainage area comprises of approximately 276.7 hectares

- Approximate proportions of land uses within the watershed are as follows:
 - Agricultural: 74%
 - Woodlot: 19%
 - Roads: 5%
 - Residential: 2%
- The Ontario Ministry of Agriculture, Food and Agribusiness's (OMAFRA's) Agricultural Information Atlas describes the soil types within the watershed and along the routes of the drains as loamy phase.

5.2 Existing Drainage System:

- The age of the original drainage system is unknown; however, it was last altered 1989.
- The existing drainage system consists of a main drain and three branch drains
 - The main drain is comprised of approximately 3,098 metres of open ditch.
 - Branch 'A' is a closed drainage system of approximately 1,400 metres in length with pipe diameters ranging from 300mm to 400mm.
 - Branch 'A' also includes a 300mm diameter, 7.5 horsepower pump.
 - Branch 'B' is a closed drainage system of approximately 288 metres in length and consists of 200mm diameter pipe.
 - Branch 'C' is a closed drainage system of approximately 75 metres in length and consists of 200mm diameter pipe.

5.3 Outlet:

- The outlet for the Shafley Municipal Drain is the Big Forks Drain on the west side of Smith Road, Lot 36, Concession 5.
- The Big Forks Drain is of adequate depth to provide sufficient outlet for the Shafley Municipal Drain. Likewise, no construction works are proposed in the Big Forks Drain under this report.

5.4 Other Noted Observations:

- The existing drainage system has very flat grades, increasing the need for frequent maintenance.
- The drain is not of sufficient depth to provide drainage at today's standards for lands within the watershed.
- Additional systematic tiling within the watershed is likely. For some lands, the capital cost of achieving a gravity outlet may make private pumping a more practical option.



- Portions of the Smith Road alongside the Shafley Drain, located downstream of Wilford Road have been reported to exhibit signs of instability.
- Some of the existing culverts are in poor states of repair and are of insufficient size and depth to convey runoff from upstream lands at today's standards of drainage.

5.5 Environmental Findings:

- The Department of Fisheries and Oceans (DFO) has classified Shafley Road Drain (Open) as "F Class", according to the OMAFA Agricultural Information Atlas, indicating an intermittently flowing watercourse with low fish habitat value.

6.0 DESIGN CONSIDERATIONS

6.1 Design Concepts Considered

Several design concepts were evaluated over the course of the design process. These options were developed in response to project needs, Landowner and Stakeholder direction, railway and Township input. The major alternatives considered are summarized below.

6.1.1 Maintain the Existing Configuration, with Upgrades

The initial concept retained the general configuration of the existing system. This option involved deepening the entire Shafley Municipal Drain, including replacement and deepening of the Canadian Pacific (CP) Rail culvert. Branch 'A' would also be deepened and upsized, which would require a new railway crossing and a larger pump installation at the lower end of Branch 'A'.

Railway requirements were reviewed at the June 28, 2023 meeting. The railway confirmed that the improved works could proceed provided safety and construction standards were met and the costs were borne by the drainage project (not the railway company). At the time, a province-wide legal dispute concerning railway cost responsibility was ongoing. Given the uncertainty, stakeholders discussed whether to wait for the outcome of the court case or proceed along an alternate path. At the Stakeholder Meeting No. 2 (November 3, 2023), the proponent and the Township indicated a preference to move forward and look at alternate concepts.

6.1.2 Deepening (Without CP Rail Culvert Replacement)

Recognizing that coordination with CP Rail for two rail crossings would be unpractical, a revised concept was developed that minimized work at the rail crossings. Under this option, the Shafley Drain would still be deepened, though to a lesser extent than in the initial concept. The Homan lands' subsurface waters north of the railway would be redirected east to drain into the Shafley Drain (rather than to the south through the rail corridor), requiring a pump installation adjacent to Smith Road.

6.1.3 Outlet to the Collver Drain (Preferred Option)

The third concept investigated involved directing sub-surface drainage from the Homan lands north of the CP Rail corridor westward to the proposed improvements on the Collver Drain. This eliminated the need for both a CP Rail culvert replacement and a pump along Smith Road. This option was determined to be the preferred approach.



6.2 Open Ditch Work:

The open ditch works have been designed to provide adequate depth for sufficient outlets to existing private tile drains, and improved tile drainage for workable areas adjacent to and upstream of the municipal drain. Where reasonable depth could be achieved, gravity drainage has been accommodated; however, given the local topography, some localized areas may not have enough elevation difference for a gravity outlet and may require private pumping.

Provisions have been made in the proposed works to allow for the repair of areas of ditch that have experienced bank failure, erosion or slumping.

6.3 Culverts:

Access crossing culverts have been designed using a minimum event standard of a 5-year rainfall event, while the road culverts were designed using a minimum event standard of a 10-year rainfall event.

6.4 Wetlands

The drainage system is designed to function collaboratively with the natural drainage features of the nearby wetlands. The design does not include any measures intended to alter or lower wetland water levels, and no changes have been introduced that increase this capability.

7.0 ENVIRONMENTAL CONSIDERATIONS

7.1 Department of Fisheries and Oceans (DFO)

The DFO has reviewed the Request for Review package sent to them on February 21, 2025, and considered in their review information presented during discussions and meetings that were held between Headway Engineering staff and DFO personnel on November 7, 2025.

7.2 Niagara Peninsula Region Conservation Authority (NPRCA)

The NPRCA has been included on the circulation list for this report and has been invited to all public engagements. Additionally, a permit application was submitted to the NPRCA on October 8, 2025.

7.3 Ministry of Natural Resources (MNR)

Headway Engineering completed a review of the Natural Heritage Information Centre mapping for Species at Risk in Ontario. NHIC mapping indicates the potential presence of Provincial Species at Risk within approximately one kilometer of the work area. Their occurrence within the project footprint is unlikely, as the preferred habitats for the identified species do not correspond with the conditions present at the work location and are instead associated with areas farther removed.

8.0 RECOMMENDATIONS

Headway Engineering recommends the following:

1. Approximately 2,995 metres be cleaned out and/or deepened to provide sufficient outlets for existing private farm tiling systems within the watershed,
2. The installation of three access culverts, two road culverts, and two culvert extensions.



3. Bank repair or bank reinforcement as required.
4. New maintenance schedules be provided for the Shafley Drain (Open) and the proposed culverts along the drain.
5. The existing length of Branch 'A' north of the railway and Branch 'C' of the Shafley Drain on the Dirk and Akke Homan (Roll No. 12-184) and Hihojo Ltd. property (Roll. No. 12-183-01) shall be abandoned.
6. The improved drainage system be known as the **Shafley Municipal Drain**.
7. Headway Engineering also recommends the watersheds of the surrounding municipal drainage systems be updated when those drainage works require improvement in the future.

9.0 SUMMARY OF PROPOSED WORKS

The proposed work consists of:

1. The cleanout and/or deepening of approximately 2,995 metres of open ditch on the Shafley Drain.
2. The installation of three access culverts.
3. The installation of two road culverts.
4. The installation of two culvert extensions.
5. Bank repair and reinforcement (provisional).

10.0 WORKING AREA AND ACCESS

Access to the working area shall be designated by the Landowners.

The working area shall be in accordance with the following average widths. The working width may be used for construction purposes including transporting excavated soil and supplying construction materials and equipment to the site.

Drain Segment and Station Range	Property Roll No.	Working side	Average Working Width for Construction	Average Working Width for Future Maintenance
0+020 to 1+048	12-179, 12-079-01, 12-178	West	12m	10m
1+062 to 1+495	12-177	East	12m	10m
1+523 to 1+730	12-176	East	12m	10m
1+730 to 1+922	Smith Road	West	6m	6m
1+937 to 2+162	12-179-15, 12-180-01	West	12m	10m
2+162 to 2+202	Smith Road	East	6m	6m



2+202 to 2+959	12-180	West	12m	10m
2+973 to 3+095	12-172	East	12m	10m

Table 3 - Summary of Working Area Descriptions

11.0 SCHEDULES

Four schedules are attached and form part of this report.

11.1 Schedule A – Schedule of Allowances

In accordance with Sections 29 and 30 of the Drainage Act, allowances are provided to affected Landowners for Right-of-Way, Damages to Lands and Crops and Loss of Access. Schedule A contains a table of the applicable allowances to Landowners.

11.2 Schedule B – Schedule of Estimated Construction Costs

An itemized cost estimate of the proposed construction work is included in detail in Schedule B.

11.3 Schedule C – Schedule of Assessment for Construction

Schedule C provides details of the distribution of the total estimated costs of the construction of the municipal drain.

11.4 Schedule D – Schedule of Assessment for Maintenance

Schedule D provides details of the distribution of future maintenance costs for the municipal drain. Maintenance assessments are expressed as a percentage of the total maintenance. Lands located upstream of the maintenance shall be determined by the Drainage Superintendent and assessed according to this schedule.

12.0 ALLOWANCES

In accordance with Sections 29 and 30 of the Drainage Act, Allowances payable to Landowners are calculated using the following methodology.

12.1 Allowances for Right-of-Way (Section 29)

The Right-of-Way allowance compensates the lands for the right to enter onto the land at various times for the purpose of inspecting the drainage system and conducting maintenance activities.

The values used for calculating allowances for Right-of-Way are as follows:

Land Use	Land Value	Adjustment Factor for Drainage Act Right-of-Way	Adjusted Land Value for Drainage Act Right-of-Way Allowance
Agricultural Working Side of Ditch	\$50,000/Ha	25%	\$12,500/Ha
Agricultural Additional Top Width	\$50,000/Ha	100%	\$50,000/Ha



Woodlot Working Side of Ditch	\$15,000/Ha	25%	\$3,750/Ha
Woodlot Additional Top Width	\$15,000/Ha	100%	\$15,000/Ha

Table 4 - Land Values and Right-of-Way Allowances

12.2 Allowances for Damages to Lands and Crops (Section 30)

Allowances for Damages to Lands and Crops under Section 30 of the Drainage Act, were primarily calculated to compensate landowners for crop losses, bush losses and land damages due to the construction and operation of the drain, including access to the working area.

Area values used for calculating allowances for Damages are as follows:

Land Use	Damage Value
Agricultural	\$6,000/Ha
Woodlot	\$3,000/Ha.

Table 5 - Standard Land Damage Values

Allowances payable to Landowners entitled thereto are as shown in Schedule A.

Total Allowances, under Sections 29, and 30 of the Drainage Act;

Shafley Municipal Drain: \$ 60,720

13.0 ESTIMATED CONSTRUCTION COSTS

Headway Engineering has made an estimate of the cost of the proposed construction work. A detailed description of the estimated construction costs can be found in Schedule B of this report.

A) Shafley Drain	\$ 388,240
B) Provisional Items	\$ 25,000
Total Estimated Construction Costs	<u>\$ 413,240</u>

14.0 SUMMARY OF ESTIMATED PROJECT COSTS

The total estimated project costs are as follows:

Allowances under Sections 29 and 30 of the Drainage Act (Refer to Schedule A)	\$ 60,720
Total Estimated Construction Costs (Refer to Schedule B)	\$ 413,240
Meetings, survey, design, preparation of preliminary cost estimates, preparation of final drainage report, consideration of report	\$ 75,900
Consultation with Environmental Agencies and Permitting Fees	\$ 2,500



Preparation of contract documents, contract administration, supervision, and inspection of construction	\$ 36,700
Contingencies, Interest and net H.S.T.	\$ 37,540
TOTAL ESTIMATED PROJECT COSTS – SHAFLEY MUNICIPAL DRAIN	\$626,600

The estimated cost of the work in the Township of Wainfleet is \$ 626,600.

The above costs are estimates only. The final costs of construction, engineering and administration cannot be determined until construction is completed.

The above cost estimate does not include costs associated with defending the drainage report should appeals be filed with the Court of Revision, Drainage Tribunal and/or Drainage Referee. Should additional costs be incurred, unless otherwise directed, the additional costs would be distributed in a pro-rata fashion over the assessments contained in Schedule C and as may be varied under the Drainage Act.

15.0 ASSESSMENT

Headway Engineering assesses the cost of this work against the Lands and Roads as shown in Schedule C - Assessment for Construction.

Assessments were determined using the principles included in the 'Drainage Assessment Revisited' paper prepared by E.P. Dries and H.H. Todgham. These principles of assessment are recognized to be fair and equitable for determining cost distributions among those affected.

15.1 Benefit (Section 22)

Benefit assessment is applied to those properties receiving a benefit as defined in Section 1 of the Drainage Act which is extracted below:

Benefit means the advantages to any lands, roads, buildings or other structures from the construction, improvement, repair, or maintenance of a drainage works such as will result in a higher market value or increased crop production or improved appearance or better control of surface or sub-surface water, or any other advantages relating to the betterment of lands, roads, buildings or other structures.

Typically, properties which have direct, or near direct access to the proposed drain receive Benefit as defined above.

15.2 Outlet Liability (Section 23)

Outlet Liability is distributed to all properties within the watershed area on an adjusted area basis. The areas are adjusted to accurately reflect equivalent run-off rates relative to other lands and roads within the watershed. Due to development, roads have been assessed higher Outlet Liability rates relative to agricultural lands.

15.3 Special Benefit (Section 24)

The Special Benefit instrument of assessment was used to separate the benefit portion of the new culvert crossings from the remaining costs of the new crossings.



15.4 Special Assessment (Section 26)

Special Assessments apply to public utilities and roads which directly cause increased costs to the construction of a drainage works due to the existence and operation of the public utility or road.

Construction costs which are required solely because of the existence of Smith Road are fully assessed to the road authority having jurisdiction over the road. The Special Assessment is calculated based on the actual costs of the proposed work, plus an allowance for administration, interest and Net HST as described below.

Road Name	Estimated Construction Costs	Plus, Estimated Administration Costs	Less Equivalent Drain Costs (Fixed)	Plus, Estimated Interest, and Net HST	Estimated Special Assessment
Smith Road 1+930	\$29,500	\$6,700	\$800	\$1,300	\$36,700
Smith Road 2+967	\$24,800	\$6,410	\$900	\$1,190	\$31,500

Table 6 - Estimated Special Assessment Calculations.

Whether or not the Township of Wainfleet elects to do the work along Smith Road they shall be assessed the actual increased costs to the drainage works due to the construction and operation of the above-mentioned sections of the Shafley Municipal Drain as a Special Assessment in addition to any benefit and outlet liability assessments.

If any additional work is required to construct or maintain the drainage works due to the existence of buried utilities, roads, railways, or if utilities require relocation or repair, then the extra costs incurred shall be borne by the utility, road or railway involved in accordance with the provisions of Section 26 of the Drainage Act.

16.0 GRANT ELIGIBILITY

The Province of Ontario provides grants towards assessments to eligible properties for drainage improvements which meet specified criteria. The provision of these grants for activities under the Drainage Act is called the Agriculture Drainage Infrastructure Program (ADIP).

A grant may be available for assessments to privately owned parcels of land which are used for agricultural purposes and eligible for Farm Property Class Tax rate. Section 88 of the Drainage Act directs the Municipality to make application for this grant upon certification of completion. The Municipality will then deduct the grant from the assessments.

Grant values provided by the Province of Ontario are for one-third (1/3) of the total assessment for eligible properties.

17.0 ABANDONMENT OF EXISTING MUNICIPAL DRAINS

In accordance with Section 19 of the Drainage Act, the existing municipal tile drainage system for Branch 'A' north of the railway and Branch 'C', constructed under the authority of a report prepared in 1989, shall be abandoned.



18.0 MAINTENANCE

After completion, this drain shall be maintained by the Township of Wainfleet at the expense of all the lands and roads assessed in the attached Schedule D - Assessment for Future Maintenance, and in the same relative proportions until such time as the assessment is changed under the Drainage Act, except for those portions of the drainage works crossing municipal or rail right-of-ways. These portions of the drain shall be maintained at the expense of the road authority having jurisdiction over said road. Culvert sizes for the private crossings not being replaced under this report have been included in the drawing set for reference. Landowners and railway agencies are recommended to use these details when undertaking future replacements.



Schedule A

Schedule of Allowances

Schedule of Allowances Shafley Municipal Drain

Shafley Municipal Drain	Property Details				Drairage Act Allowances		
	Part Lot	Con.	Landowner	Roll Number	Right of Way (Sec. 29)	Damages (Sec. 30)	Total Allowances
	Pt. 35	5	R. & L. Marr	12-177	\$ 7,580	\$ 3,120	\$ 10,700
	Pt. 36	5	Vision Farms Ltd.	12-079	\$ 7,830	\$ 4,220	\$ 12,050
	Pt. 36	5	D. & A. Homan	12-079-01	\$ 3,410	\$ 2,170	\$ 5,580
	Pt. 36	5	J. & J. Homan	12-178	\$ 110	\$ 500	\$ 610
	Pt. 35	6	D. & M. Vander Meer	12-176	\$ 2,590	\$ 2,490	\$ 5,080
	Pt. 35	6	Vander Meer Farms Ltd.	12-172	\$ 2,140	\$ 880	\$ 3,020
	Pt. 35	6	A. Amanali & N. Merchant	12-174	\$ -	\$ 1,010	\$ 1,010
	Pt. 35	6	K. & T. Vis	12-175	\$ -	\$ 870	\$ 870
	Pt. 35	6	J. & E. Vanamerongen	12-173-50	\$ -	\$ 670	\$ 670
	Pt. 36	6	Hihojo Ltd.	12-179-15	\$ 2,240	\$ 920	\$ 3,160
	Pt. 36	6	K. Perron	12-180-01	\$ 2,180	\$ 1,990	\$ 4,170
	Pt. 36	6	Y. Hessels	12-180	\$ 9,230	\$ 4,570	\$ 13,800
	Total Allowances						
	Shafley Municipal Drain				\$ 37,310	\$ 23,410	\$ 60,720



Schedule B

Schedule of Estimated Construction Costs

Schedule of Estimated Construction Costs

An estimate of the cost of the proposed work has been completed, which is outlined in detail as follows:

Part A - Shafley Municipal Drain

Description	Estimated Quantity	\$/Unit	Total
1) Clearing, brushing and mulching	l.s.		\$ 40,000.00
2) Open ditch excavation (approx. 4,600m3)	2995 m	\$ 20.00	\$ 59,900.00
3) Hydro seed disturbed side slopes	7500 m2	\$ 4.00	\$ 30,000.00
4) Supply 1-1600mm diameter, corrugated steel pipe laneway culvert (Homan Crossing), 2.8mm thickness, 125x25mm corrugations, aluminized Type II coating	45 m	\$ 1,000.00	\$ 45,000.00
Installation of 1600mm diameter culvert at Sta. 0+606 complete with quarry stone rip-rap protection and geotextile material (25m2) including remove and dispose of existing culvert offsite and connection of 375mm road pipe.	l.s.		\$ 22,500.00
5) Supply 1-900mm diameter, corrugated steel pipe laneway culvert (Perron Crossing), 2.0mm thickness, 68x13mm corrugations, aluminized Type II coating	12 m	\$ 450.00	\$ 5,400.00
Installation of 900mm diameter culvert at Sta. 2+189 complete with quarry stone rip-rap protection and geotextile material (20m2) including remove and dispose of existing culvert offsite	l.s.		\$ 7,000.00
6) Supply 1-900mm diameter, corrugated steel pipe laneway culvert (Hessels Crossing), 2.0mm thickness, 68x13mm corrugations, aluminized Type II coating	12 m	\$ 450.00	\$ 5,400.00
Installation of 900mm diameter culvert at Sta. 2+460 complete with quarry stone rip-rap protection and geotextile material (20m2) including remove and dispose of existing culvert offsite	l.s.		\$ 7,000.00
7) Erosion and sediment control	l.s.		\$ 5,000.00

<u>Description</u>	<u>Estimated Quantity</u>	<u>\$/Unit</u>	<u>Total</u>
8) Supply 1-1200mm diameter, corrugated steel pipe culvert, 2.8mm thickness, 125x25mm corrugations, aluminized Type II coating Installation of 1200mm diameter culvert including connections to existing culverts Sta. 0+020 to Sta. 0+046 and Sta. 0+100 to Sta.0+145 complete with quarry stone rip-rap protection and geotextile material (25m2)	71 m	\$ 800.00	\$ 56,800.00
	I.s.		\$ 35,000.00
9) Traffic Control	I.s.		<u>\$ 14,940.00</u>
Sub-Total - Work on the Township of Wainfleet Road Allowance (Non-Special Assessment)			<u>\$ 333,940.00</u>
<hr/>			
10) Work on the Township of Wainfleet Road Allowance (Smith Road Crossing), (Sta. 1+922 to Sta. 1+937)			
<hr/>			
a) Supply 1-1200mm diameter, corrugated steel pipe road culvert, 2.8mm thickness, 125x25mm corrugations, aluminized Type II coating Installation of 1200mm diameter culvert at Sta. 2+966 complete with quarry stone rip-rap protection and geotextile material (xxm2) including remove and dispose of existing culvert offsite	16 m	\$ 800.00	\$ 12,800.00
	I.s.		\$ 10,000.00
b) Road Restoration including: Supply and Place 150mm thickness of Granular 'A' (50m2 x 0.15m thickness)	20 t	\$ 60.00	\$ 1,200.00
HL8 and 50mm HL4) asphalt (40m2 x 0.1m thickness)	10 t	\$ 500.00	\$ 5,000.00
c) Traffic Control	I.s.		\$ 500.00
Sub-Total - Work on the Township of Wainfleet Road Allowance (Smith Road - Special Assessment)			<u>\$ 29,500.00</u>

Description	Estimated Quantity	\$/Unit	Total
10) Work on the Township of Wainfleet Road Allowance (Smith Road Crossing), (Sta. 2+960 to Sta. 2+974)			
a) Supply 1-900mm diameter, corrugated steel pipe road culvert, 2.0mm thickness, 68x13mm corrugations, aluminized Type II coating	18 m	\$ 450.00	\$ 8,100.00
Installation of 900mm diameter culvert at Sta. 2+967 complete with quarry stone rip-rap protection and geotextile material (xxm2) including remove and dispose of existing culvert offsite	I.s.		\$ 10,000.00
b) Road Restoration including:			
Supply and Place 150mm thickness of Granular 'A' (50m2 x 0.15m thickness)	20 t	\$ 60.00	\$ 1,200.00
Supply and place 100mm thickness (50mm HL8 and 50mm HL4) asphalt (40m2 x 0.1m thickness)	10 t	\$ 500.00	\$ 5,000.00
c) Traffic Control	I.s.		\$ 500.00
Sub-Total - Work on the Township of Wainfleet Road Allowance (Smith Road - Special Assessment)			\$ 24,800.00

Total Estimated Construction Costs

Part A - Shafley Municipal Drain **\$ 388,240.00**

Part B - Provisional Items

A Provisional Item is an item that may or may not be required as a part of the Contract. The decision as to whether a Provisional Item will form part of the Contract will be at the discretion of the engineer at time of construction. Payment for Provisional Items will only be made for work authorized in writing by the Engineer. Payment for work performed under a Provisional Item shall be based on the Unit Price bid in the Scope of Work below.

1) Quarry stone rip-rap including geotextile filter material	250 t	\$ 100.00	\$ 25,000.00
--	-------	-----------	--------------

Total Estimated Construction Costs

Part B - Provisional Items **\$ 25,000.00**

Summary of Estimated Construction Costs

Part A - Shafley Municipal Drain	\$	388,240.00
Part B - Provisional Items	\$	<u>25,000.00</u>

Total Estimated Construction Costs **\$** **413,240.00**

Total Estimated Materials	\$	133,500.00
Total Estimated Labour and Equipment	\$	<u>279,740.00</u>

Total Estimated Construction Costs
SHAFLEY MUNICIPAL DRAIN **\$** **413,240.00**



Schedule C

Schedule of Assessment for Construction

**Schedule of Assessment for Construction
Shafley Municipal Drain**

Property Details						Drainage Act Instruments of Assessment				For Information		
Part Lot	Concession	Landowner	Roll Number	Approx. Ha. Affected	Benefit (Sec. 22)	Outlet Liability (Sec. 23)	Special Benefit (Sec. 24)	Special Assessment (Sec. 26)	Total Assessment	Less Gov't Grant	Less Allowances	Net Estimated Expense
Pt. 34	5	S. Scheel & K. Comfort	12-167	0.7	\$ -	\$ 32			\$ 32	*	\$ -	\$ 32
Pt .34	5	R. & L. Marr	12-167-02	2.5	\$ -	\$ 121			\$ 121	*	\$ -	\$ 121
Pt. 35	5	Hihojo Ltd.	12-077	0.3	\$ -	\$ 57			\$ 57	\$ 19	\$ -	\$ 38
Pt. 35	5	2027479 Ontario Ltd.	12-077-01	8.7	\$ -	\$ 1,366			\$ 1,366	\$ 455	\$ -	\$ 911
Pt. 35	5	L. & L. Dumlao	12-078	0.9	\$ -	\$ 355			\$ 355.00	*	\$ -	\$ 355
Pt. 35	5	R. & L. Marr	12-177	17.7	\$ 24,731	\$ 3,673			\$ 28,404	*	\$ 10,700	\$ 17,704
Pt. 36	5	Vision Farms Ltd.	12-079	5.0	\$ 25,162	\$ 504	\$ 4,580		\$ 30,246	\$ 10,082	\$ 12,050	\$ 8,114
Pt. 36	5	D. & A. Homan	12-079-01	8.1	\$ 6,641	\$ 251	\$ 13,740		\$ 20,632	\$ 6,877	\$ 5,580	\$ 8,175
Pt. 36	5	J. & J. Homan	12-178	27.9	\$ 7,793	\$ 11,677			\$ 19,470	\$ 6,490	\$ 610	\$ 12,370
Pt. 37	5	J. Homan	12-178-01	0.8	\$ -	\$ 269			\$ 269	\$ 90	\$ -	\$ 179
Pt. 37	5	Hihojo Ltd.	12-183	8.4	\$ -	\$ 2,435			\$ 2,435	\$ 812	\$ -	\$ 1,623
Pt. 34	6	A. & C. Otten	12-168	20.6	\$ -	\$ 9,975			\$ 9,975	\$ 3,325	\$ -	\$ 6,650
Pt. 34	6	L. Ireland	12-168-01	5.9	\$ -	\$ 1,250			\$ 1,250	*	\$ -	\$ 1,250
Pt. 34	6	N. & E. Gill	12-169	3.7	\$ -	\$ 933			\$ 933	\$ 311	\$ -	\$ 622
Pt. 35	6	D. & M. Vander Meer	12-176	10.3	\$ 22,733	\$ 5,494			\$ 28,227	\$ 9,409	\$ 5,080	\$ 13,738
Pt. 35	6	Vander Meer Farms Ltd.	12-172	30.0	\$ 23,895	\$ 26,947			\$ 50,842	\$ 16,947	\$ 3,020	\$ 30,875
Pt. 35	6	R. Anderson	12-171	20.5	\$ -	\$ 16,785			\$ 16,785	\$ 5,595	\$ -	\$ 11,190
Pt. 35	6	A. Amanali & N. Merchant	12-174	0.7	\$ 949	\$ 704			\$ 1,653	*	\$ 1,010	\$ 643
Pt. 35	6	K. & T. Vis	12-175	0.3	\$ 641	\$ 401			\$ 1,042	*	\$ 870	\$ 172
Pt. 35	6	J. & E. Vanamerongen	12-173-50	1.3	\$ 296	\$ 1,028			\$ 1,324	*	\$ 670	\$ 654
Pt. 35	6	R. Vangeel	12-172-02	0.4	\$ -	\$ 542			\$ 542	*	\$ -	\$ 542
Pt. 36	6	N. Masi & A. Stephanie	12-179-05	1.4	\$ -	\$ 907			\$ 907	*	\$ -	\$ 907
Pt. 36	6	Hihojo Ltd.	12-179-15	19.1	\$ 8,957	\$ 4,717			\$ 13,674	\$ 4,558	\$ 3,160	\$ 5,956
Pt. 36	6	R. & L. Gerrys	12-179	0.7	\$ -	\$ 635			\$ 635	*	\$ -	\$ 635
Pt. 36	6	K. Perron	12-180-01	1.9	\$ 422	\$ 858	\$ 10,500		\$ 11,780	*	\$ 4,170	\$ 7,610
Pt. 36	6	T. & Y. Hessels	12-181	15.8	\$ 8,488	\$ 7,319			\$ 15,807	\$ 5,269	\$ -	\$ 10,538
Pt. 36	6	Y. Hessels	12-180	12.3	\$ 30,237	\$ 8,023	\$ 10,500		\$ 48,760	\$ 16,253	\$ 13,800	\$ 18,707
Pt. 37	6	D. & A. Homan	12-184	20.2	\$ -	\$ 1,553			\$ 1,553	\$ 518	\$ -	\$ 1,035
Pt. 37	6	Hihojo Ltd.	12-183-01	10.4	\$ -	\$ 865			\$ 865.00	\$ 288.00	\$ -	\$ 577.00
Pt. 37	6	W. Dobrucki	12-182	8.5	\$ -	\$ 907			\$ 907	\$ 302	\$ -	\$ 605
Pt. 36	7	D. & L. Mann	12-229	1.0	\$ -	\$ 968			\$ 968	\$ 323	\$ -	\$ 645
Total Assessments on Lands					\$ 160,945	\$ 111,551	\$ 39,320	\$ -	\$ 311,816	\$ 87,923	\$ 60,720	\$ 163,173

Shafley Municipal Drain	Property Details				Drainage Act Instruments of Assessment				For Information			
	Road Name	Road Authority	Roll Number	Approx. Ha. Affected	Benefit (Sec. 22)	Outlet Liability (Sec. 23)	Special Benefit (Sec. 24)	Special Assessment (Sec. 26)	Total Assessment	Less Gov't Grant	Less Allowances	Net Estimated Expense
	Zion Road	Township of Wainfleet		0.8	\$ -	\$ 1,331			\$ 1,331			\$ 1,331
	Smith Road	Township of Wainfleet		5.2	\$ 34,203	\$ 13,106	\$ 160,860	\$ 68,200	\$ 276,369			\$ 276,369
	Marr Road	Township of Wainfleet		1.0	\$ -	\$ 4,032			\$ 4,032			\$ 4,032
	Gracey Road	Township of Wainfleet		0.1	\$ -	\$ 252			\$ 252			\$ 252
	Willford Road	Township of Wainfleet		1.3	\$ 6,487	\$ 3,460			\$ 9,947			\$ 9,947
	Canada Southern Railway Company		13-998	4.2	\$ 4,897	\$ 10,585			\$ 15,482			\$ 15,482
	Concession 6 Road	Township of Wainfleet		0.8	\$ 838	\$ 6,533			\$ 7,371			\$ 7,371
	Total Assessments on Roads				\$ 46,425	\$ 39,299	\$ 160,860	\$ 68,200	\$ 314,784			\$ 314,784
	Total Assessments Shafley Municipal Drain				\$ 207,370	\$ 150,850	\$ 200,180	\$ 68,200	\$ 626,600	\$ 87,923	\$ 60,720	\$ 477,957

- Notes:
- 1 '*' Denotes Lands not eligible for ADIP Grants.
 - 2 The Special Benefit Assessment (Sec. 24) has been used to separate the benefit portion of culvert crossings from the normal benefit assessment.
 - 3 The Special Assessments (Sec. 26) shall be a non-proratable assessment. All other assessments are proratable.
 - 4 The Net Estimated Expense is the Total Assessment less gov't grants and allowances (if applicable).



Schedule D

Schedule of Assessment for Future Maintenance

Schedule of Assessment for Future Maintenance Shafley Municipal Drain

Shafley Municipal Drain	Property Details					Proportion of Maintenance Assessment			
						Open Ditch	Municipal Drain Crossings		
	Part Lot	Con.	Landowner	Roll Number		Shafley Drain (Open)	Sta. 0+606	Sta. 2+189	Sta. 2+460
	Pt. 34	5	S. Scheel & K. Comfort	12-167	*	0.02%	0.003%		
	Pt. 34	5	R. & L. Marr	12-167-02	*	0.08%	0.01%		
	Pt. 35	5	Hihojo Ltd.	12-077		0.04%	0.01%		
	Pt. 35	5	2027479 Ontario Ltd.	12-077-01		0.91%	0.06%		
	Pt. 35	5	L. & L. Dumlao	12-078		0.24%	0.05%		
	Pt. 35	5	R. & L. Marr	12-177	*	2.43%	0.50%		
	Pt. 36	5	Vision Farms Ltd.	12-079		0.33%	5.56%		
	Pt. 36	5	D. & A. Homan	12-079-01		0.17%	16.73%		
	Pt. 36	5	J. & J. Homan	12-178		7.74%	1.69%		
	Pt. 37	5	J. Homan	12-178-01		0.18%	0.04%		
	Pt. 37	5	Hihojo Ltd.	12-183		1.61%	0.35%		
	Pt. 34	6	A. & C. Otten	12-168		6.61%	1.04%		
	Pt. 34	6	L. Ireland	12-168-01	*	0.83%	0.29%		
	Pt. 34	6	N. & E. Gill	12-169		0.62%	1.08%		
	Pt. 35	6	D. & M. Vander Meer	12-176		3.64%	0.52%		
	Pt. 35	6	Vander Meer Farms Ltd.	12-172		17.86%	1.79%	11.30%	12.42%
	Pt. 35	6	R. Anderson	12-171		11.13%	0.94%	5.94%	8.65%
	Pt. 35	6	A. Amanali & N. Merchant	12-174	*	0.47%	0.06%		
	Pt. 35	6	K. & T. Vis	12-175	*	0.27%	0.03%		

Shafley Municipal Drain	Property Details					Proportion of Maintenance Assessment			
	Part Lot	Con.	Landowner	Roll Number	*	Open Ditch	Municipal Drain Crossings		
						Shafley Drain (Open)	Sta. 0+606	Sta. 2+189	Sta. 2+460
	Pt. 35	6	J. & E. Vanamerongen	12-173-50	*	0.68%	0.08%		
	Pt. 35	6	R. Vangeel	12-172-02	*	0.36%	0.03%	0.17%	0.23%
	Pt. 36	6	N. Masi & A. Stephanie	12-179-05	*	0.60%	0.09%		
	Pt. 36	6	Hihojo Ltd.	12-179-15		3.13%	0.59%		
	Pt. 36	6	R. & L. Gerrys	12-179	*	0.42%	0.05%		
	Pt. 36	6	K. Perron	12-180-01	*	0.57%	0.06%	70.00%	
	Pt. 36	6	T. & Y. Hessels	12-181		4.85%	0.47%	4.80%	
	Pt. 36	6	Y. Hessels	12-180		5.32%	0.45%	2.86%	75.09%
	Pt. 37	6	D. & A. Homan	12-184		1.03%	0.38%		
	Pt. 37	6	Hihojo Ltd.	12-183-01		0.57%	0.25%		
	Pt. 37	6	W. Dobrucki	12-182		0.60%	0.12%		
	Pt. 36	7	D. & L. Mann	12-229		0.64%	0.05%	0.29%	0.40%
	Total Assessments on Lands					73.95%	33.39%	95.37%	96.80%
	Zion Road		Township of Wainfleet			0.88%	0.19%		
	Smith Road		Township of Wainfleet			8.69%	64.20%	2.58%	0.41%
	Marr Road		Township of Wainfleet			2.67%	0.38%		
	Gracey Road		Township of Wainfleet			0.17%	0.01%	0.08%	0.10%
	Willford Road		Township of Wainfleet			2.29%	0.50%		
	Canada Southern Railway Company					7.02%	1.01%		
	Concession 6 Road		Township of Wainfleet			4.33%	0.31%	1.97%	2.68%
	Total Assessments on Roads					26.05%	66.61%	4.63%	3.20%
	Total Assessments Shafley Municipal Drain					100.00%	100.00%	100.00%	100.00%



Specifications for the Construction of Municipal Drainage Works

DIVISION A – General Conditions

DIVISION B – Specification for Open Drains

DIVISION H – Special Provisions



DIVISION A

General Conditions



CONTENTS

A.1.	SCOPE.....	1
A.2.	TENDERS.....	1
A.3.	EXAMINATIONS OF SITE, DRAWINGS, AND SPECIFICATIONS.....	1
A.4.	PAYMENT	2
A.5.	CONTRACTOR’S LIABILITY INSURANCE	2
A.6.	LOSSES DUE TO ACTS OF NATURE, ETC.....	2
A.7.	COMMENCEMENT AND COMPLETION OF WORK.....	2
A.8.	WORKING AREA AND ACCESS.....	3
A.9.	SUB-CONTRACTORS	3
A.10.	PERMITS, NOTICES, LAWS AND RULES.....	3
A.11.	RAILWAYS, HIGHWAYS, AND UTILITIES	3
A.12.	ERRORS AND UNUSUAL CONDITIONS.....	3
A.13.	ALTERATIONS AND ADDITIONS.....	3
A.14.	SUPERVISION	4
A.15.	FIELD MEETINGS.....	4
A.16.	PERIODIC AND FINAL INSPECTIONS.....	4
A.17.	ACCEPTANCE BY THE MUNICIPALITY	4
A.18.	WARRANTY.....	4
A.19.	TERMINATION OF CONTRACT BY THE MUNICIPALITY	4
A.20.	TESTS.....	5
A.21.	POLLUTION	5
A.22.	SPECIES AND RISK.....	5
A.23.	ROAD CROSSINGS.....	5
A.23.1.	ROAD OCCUPANCY PERMIT	5
A.23.2.	ROAD CLOSURE REQUEST AND CONSTRUCTION NOTIFICATION	6
A.23.3.	TRAFFIC CONTROL.....	6
A.23.4.	WEATHER.....	6
A.23.5.	EQUIPMENT	6
A.24.	LANEWAYS.....	6



A.25.	FENCES	7
A.26.	LIVESTOCK	7
A.27.	STANDING CROPS.....	7
A.28.	SURPLUS GRAVEL	7
A.29.	IRON BARS	7
A.30.	RIP-RAP	7
A.31.	CLEARING, GRUBBING AND BRUSHING	8
A.32.	RESTORATION OF LAWNS	8



DIVISION A – GENERAL CONDITIONS

A.1. Scope

The work to be done under this contract consists of supplying all labour, equipment and materials to construct the drainage work as outlined in the Scope of Work, Drawings, General Conditions and other Specifications.

A.2. Tenders

Tenders are to be submitted on a lump sum basis for the complete works or a portion thereof, as instructed by the Municipality. The Scope of Work must be completed and submitted with the Form of Tender and Agreement. A certified cheque is required as Tender Security, payable to the Treasurer of the Municipality.

All certified cheques, except that of the bidder to whom the work is awarded will be returned within ten (10) days after the tender closing. The certified cheque of the bidder to whom the work is awarded will be retained as Contract Security and returned when the Municipality receives a Completion Certificate for the work.

A certified cheque is not required if the Contractor provides an alternate form of Contract Security such as a Performance Bond for 100% of the amount of the Tender or other satisfactory security, if required/permitted by the Municipality. A Performance Bond may also be required to insure maintenance of the work for a period of one (1) year after the date of the Completion Certificate.

A.3. Examinations of Site, Drawings, and Specifications

The Tenderer must examine the premises and site to compare them with the Drawings and Specifications in order to satisfy himself of the existing conditions and extent of the work to be done before submission of his Tender. No allowance shall subsequently be made on behalf of the Contractor by reason of any error on his part. Any estimates of quantities shown or indicated on the Drawings, or elsewhere are provided for the convenience of the Tenderer. Any use made of these quantities by the Tenderer in calculating his Tender shall be done at his own risk. The Tenderer for his own protection should check these quantities for accuracy.

The standard specifications (Divisions B through G) shall be considered complementary and where a project is controlled under one of the Divisions, the remaining Divisions will apply for miscellaneous works.

In case of any inconsistency or conflict between the Drawings and Specifications, the following order of precedence shall apply:

- Direction of the Engineer
- Special Provisions (Division H)
- Scope of Work
- Contract Drawings
- Standard Specifications (Divisions B through G)
- General Conditions (Division A)



A.4. Payment

Progress payments equal to 87±% of the value of work completed and materials incorporated in the work will be made to the Contractor monthly. An additional ten per cent (10±%) will be paid 60 days after the final acceptance by the Engineer, and three per cent (3±%) of the Contract price may be reserved by the Municipality as a maintenance holdback for a one (1) year period from the date of the Completion Certificate. A greater percentage of the Contract price may be reserved by the Municipality for the same one (1) year period if in the opinion of the Engineer, particular conditions of the Contract requires such greater holdback.

After the completion of the work, any part of this reserve may be used to correct defects developed within that time from faulty workmanship and materials, provided that notice shall first be given to the Contractor and that he may promptly make good such defects.

A.5. Contractor's Liability Insurance

Prior to commencement of any work, the Contractor shall file with the Municipality evidence of compliance with all Municipality insurance requirements (Liability Insurance, WSIB, etc.) for no less than the minimum amounts as stated in the Purchasing Procedures of the Municipality. All insurance coverage shall remain in force for the entire contract period including the warranty period which expires one year after the date of the Completion Certificate.

The following are to be named as co-insured:

- Successful Contractor
- Sub-Contractor
- Municipality
- Headway Engineering

A.6. Losses Due to Acts of Nature, Etc.

All damage, loss, expense and delay incurred or experienced by the Contractor in the performance of the work, by reason of unanticipated difficulties, bad weather, strikes, acts of nature, or other mischances shall be borne by the Contractor and shall not be the subject of a claim for additional compensation.

A.7. Commencement and Completion of Work

The work must commence as specified in the Form of Tender and Agreement. If conditions are unsuitable due to poor weather, the Contractor may be required, at the discretion of the Engineer to postpone or halt work until conditions become acceptable and shall not be subject of a claim for additional compensation.

The Contractor shall give the Engineer a minimum of 48 hours notice before commencement of work. The Contractor shall then arrange a meeting to be held on the site with Contractor, Engineer, and affected Landowners to review in detail the construction scheduling and other details of the work.

If the Contractor leaves the job site for a period of time after initiation of work, he shall give the Engineer and the Municipality a minimum of 24 hours notice prior to returning to the project. If any work is commenced without notice to the Engineer, the Contractor shall be fully responsible for all such work undertaken prior to such notification.



The work must proceed in such a manner as to ensure its completion at the earliest possible date and within the time limit set out in the Form of Tender and Agreement.

A.8. Working Area and Access

Where any part of the drain is on a road allowance, the road allowance shall be the working area. For all other areas, the working area available to the Contractor to construct the drain is specified in the Special Provisions (Division H).

Should the specified widths become inadequate due to unusual conditions, the Contractor shall notify the Engineer immediately. Where the Contractor exceeds the specified working widths without authorization, he shall be held responsible for the costs of all additional damages.

If access off an adjacent road allowance is not possible, each Landowner on whose property the drainage works is to be constructed, shall designate access to and from the working area. The Contractor shall not enter any other lands without permission of the Landowner and he shall compensate the Landowner for damage caused by such entry.

A.9. Sub-Contractors

The Contractor shall not sublet the whole or part of this Contract without the approval of the Engineer.

A.10. Permits, Notices, Laws and Rules

The Contractor shall obtain and pay for all necessary permits or licenses required for the execution of the work (but this shall not include MTO encroachment permits, County Road permits permanent easement or rights of servitude). The Contractor shall give all necessary notices and pay for all fees required by law and comply with all laws, ordinances, rules and regulations relating to the work and to the preservation of the public's health and safety.

A.11. Railways, Highways, and Utilities

A minimum of 72 hours' notice to the Railway or Highways, exclusive of Saturdays, Sundays, and Statutory Holidays, is required by the Contractor prior to any work activities on or affecting the applicable property. In the case of affected Utilities, a minimum of 48 hours' notice to the utility owner is required.

A.12. Errors and Unusual Conditions

The Contractor shall notify the Engineer immediately of any error or unusual conditions which may be found. Any attempt by the Contractor to correct the error on his own shall be done at his own risk. Any additional cost incurred by the Contractor to remedy the wrong decision on his part shall be borne by the Contractor. The Engineer shall make the alterations necessary to correct errors or to adjust for unusual conditions during which time it will be the Contractor's responsibility to keep his men and equipment gainfully employed elsewhere on the project.

The Contract amount shall be adjusted in accordance with a fair evaluation of the work added or deleted.

A.13. Alterations and Additions

The Engineer shall have the power to make alterations in the work shown or described in the Drawings and Specifications and the Contractor shall proceed to make such changes without causing delay. In



every such case, the price agreed to be paid for the work under the Contract shall be increased or decreased as the case may require according to a fair and reasonable evaluation of the work added or deleted. The valuation shall be determined as a result of negotiations between the Contractor and the Engineer, but in all cases the Engineer shall maintain the final responsibility for the decision. Such alterations and variations shall in no way render the Contract void. No claims for a variation or alteration in the increased or decreased price shall be valid unless done in pursuance of an order from the Engineer and notice of such claims made in writing before commencement of such work. In no such case shall the Contractor commence work which he considers to be extra before receiving the Engineer's approval.

A.14. Supervision

The Contractor shall give the work his constant supervision and shall keep a competent foreman in charge at the site.

A.15. Field Meetings

At the discretion of the Engineer, a field meeting with the Contractor or his representative, the Engineer and with those others that the Engineer deems to be affected, shall be held at the location and time specified by the Engineer.

A.16. Periodic and Final Inspections

Periodic inspections by the Engineer will be made during the performance of the work. If ordered by the Engineer, the Contractor shall expose the drain as needed to facilitate inspection by the Engineer.

Final inspection by the Engineer will be made within twenty (20) days after he has received notice from the Contractor that the work is complete.

A.17. Acceptance By the Municipality

Before any work shall be accepted by the Municipality, the Contractor shall correct all deficiencies identified by the Engineer and the Contractor shall leave the site neat and presentable.

A.18. Warranty

The Contractor shall repair and make good any damages or faults in the drain that may appear within one (1) year after its completion (as dated on the Completion Certificate) as the result of the imperfect or defective work done or materials furnished if certified by the Engineer as being due to one or both of these causes; but nothing herein contained shall be construed as in any way restricting or limiting the liability of the Contractor under the laws of the Country, Province or Locality in which the work is being done. Neither the Completion Certificate nor any payment there under, nor any provision in the Contract Documents shall relieve the Contractor from his responsibility.

A.19. Termination of Contract By The Municipality

If the Contractor should be adjudged bankrupt, or if he should make a general assignment for the benefit of his creditors, or if a receiver should be appointed on account of his insolvency, or if he should refuse or fail to supply enough properly skilled workmen or proper materials after having received seven (7) days notice in writing from the Engineer to supply additional workmen or materials to commence or complete the works, or if he should fail to make prompt payment to Sub-Contractors, or for material, or labour, or persistently disregards laws, ordinances, or the instruction of the Engineer,



or otherwise be guilty of a substantial violation of the provisions of the Contract, then the Municipality, upon the certificate of the Engineer that sufficient cause exists to justify such action, may without prejudice to any other right or remedy, by giving the Contractor written notice, terminate the employment of the Contractor and take possession of the premises, and of all materials, tools and appliances thereon, and may finish the work by whatever method the Engineer may deem expedient but without delay or expense. In such a case, the Contractor shall not be entitled to receive any further payment until the work is finished. If the unpaid balance of the Contract price will exceed the expense of finishing the work including compensation to the Engineer for his additional services and including the other damages of every name and nature, such excess shall be paid by the Contractor. If such expense will exceed such unpaid balance, the Contractor shall pay the difference to the Municipality. The expense incurred by the Municipality, as herein provided, shall be certified by the Engineer.

If the Contract is terminated by the Municipality due to the Contractor's failure to properly commence the works, the Contractor shall forfeit the certified cheque bid deposit and furthermore shall pay to the Municipality an amount to cover the increased costs, if any, associated with a new Tender for the Contract being terminated.

If any unpaid balance and the certified cheque do not match the monies owed by the Contractor upon termination of the Contract, the Municipality may also charge such expense against any money which may thereafter be due to the Contractor from the Municipality.

A.20. Tests

The cost for the testing of materials supplied to the job by the Contractor shall be borne by the Contractor. The Engineer reserves the right to subject any lengths of any tile or pipe to a competent testing laboratory to ensure the adequacy of the tile or pipe. If any tile supplied by the Contractor is determined to be inadequate to meet the applicable A.S.T.M. standards, the Contractor shall bear full responsibility to remove and/or replace all such inadequate tile in the Contract with tile capable of meeting the A.S.T.M. Standards.

A.21. Pollution

The Contractor shall keep their equipment in good repair. The Contractor shall refuel or repair equipment away from open water.

If polluted material from construction materials or equipment is caused to flow into the drain, the Contractor shall immediately notify the Ministry of the Environment, and proceed with the Ministry's protocols in place to address the situation.

A.22. Species and Risk

If a Contractor encounters a known Species at Risk as designated by the MNR or DFO, the Contractor shall notify the Engineer immediately and follow the Ministry's guidelines to deal with the species.

A.23. Road Crossings

This specification applies to all road crossings (Municipality, County, Regional, or Highway) where no specific detail is provided on the drawings or in the standard specifications. This specification in no way limits the Road Authority's regulations governing the construction of drains on their Road Allowance.

A.23.1. Road Occupancy Permit



Where applicable, the Contractor must submit an application for a road occupancy permit to the Road Authority and allow a minimum of five (5) working days for its review and issuance.

A.23.2. Road Closure Request and Construction Notification

The Contractor shall submit written notification of construction and request for road closure (if applicable) to the Road Authority and the Engineer for review and approval a minimum of five (5) working days prior to proceeding with any work on the road allowance. The Contractor shall be responsible for notifying all applicable emergency services, schools, etc. of the road closure or construction taking place.

A.23.3. Traffic Control

The Contractor shall supply flagmen, and warning signs and ensure that detour routes are adequately signed in accordance with no less than the minimum standards as set out in the Ontario Traffic Manual's Book 7.

A.23.4. Weather

No construction shall take place during inclement weather or periods of poor visibility.

A.23.5. Equipment

No construction material and/or equipment is to be left within three (3) metres of the travelled portion of the road overnight or during periods of inclement weather.

If not stated on the drawings, the road crossing shall be constructed by open cut method. Backfill from the top of the cover material over the subsurface pipe or culvert to the under side of the road base shall be Granular "B". The backfill shall be placed in lifts not exceeding 300mm in thickness and each lift shall be thoroughly compacted to 98% Standard Proctor. Granular "B" road base for County Roads and Highways shall be placed to a 450mm thickness and Granular "A" shall be placed to a thickness of 200mm. Granular road base materials shall be thoroughly compacted to 100% Standard Proctor.

Where the road surface is paved, the Contractor shall be responsible for placing HL-8 Hot Mix Asphalt patch at a thickness of 50mm or of the same thickness as the existing pavement structure. The asphalt patch shall be flush with the existing roadway on each side and without overlap.

Excavated material from the trench beyond 1.25 metres from the travelled portion or beyond the outside edge of the gravel shoulder may be used as backfill in the trench in the case of covered drains. The material shall be compacted in lifts not exceeding 300mm.

A.24. Laneways

All pipes crossing laneways shall be backfilled with material that is clean, free of foreign material or frozen particles and readily tamped or compacted in place unless otherwise specified. Laneway culverts on open ditch projects shall be backfilled with material that is not easily erodible. All backfill material shall be thoroughly compacted as directed by the Engineer.

Culverts shall be bedded with a minimum of 300mm of granular material. Granular material shall be placed simultaneously on each side of the culvert in lifts not exceeding 150mm in thickness and compacted to 95% Standard Proctor Density. Culverts shall be installed a minimum of 10% of the



culvert diameter below design grade with a minimum of 450mm of cover over the pipe unless otherwise noted on the Drawings.

The backfill over culverts and subsurface pipes at all existing laneways that have granular surfaces on open ditch and closed drainage projects shall be surfaced with a minimum of 300mm of Granular “B” material and 150mm of Granular “A” material. All backfill shall be thoroughly compacted as directed by the Engineer. All granular material shall be placed to the full width of the travelled portion.

Any settling of backfilled material shall be repaired by or at the expense of the Contractor during the warranty period of the project and as soon as required.

A.25. Fences

No earth is to be placed against fences and all fences removed by the Contractor shall be replaced by him in as good a condition as found. Where practical the Contractor shall take down existing fences in good condition at the nearest anchor post and roll it back rather than cutting the fence and attempting to patch it. The replacement of the fences shall be done to the satisfaction of the Engineer. Any fences found in such poor condition where the fence is not salvageable, shall be noted and verified with the Engineer prior to commencement of work.

Fences damaged beyond repair by the Contractor’s negligence shall be replaced with new materials, similar to those materials of the existing fence, at the Contractor’s expense. The replacement of the fences shall be done to the satisfaction of the Landowner and the Engineer.

Any fences paralleling an open ditch that are not line fences that hinder the proper working of the excavating machinery, shall be removed and rebuilt by the Landowner at his own expense.

The Contractor shall not leave fences open when he is not at work in the immediate vicinity.

A.26. Livestock

The Contractor shall provide each landowner with 48 hours notice prior to removing any fences along fields which could possibly contain livestock. Thereafter, the Landowner shall be responsible to keep all livestock clear of the construction areas until further notified. The Contractor shall be held responsible for loss or injury to livestock or damage caused by livestock where the Contractor failed to notify the Landowner, or through negligence or carelessness on the part of the Contractor.

A.27. Standing Crops

The Contractor shall be responsible for damages to standing crops which are ready to be harvested or salvaged along the course of the drain and access routes if the Contractor has failed to notify the Landowners 48 hours prior to commencement of the work on that portion of the drain.

A.28. Surplus Gravel

If as a result of any work, gravel or crushed stone is required and not all the gravel or crushed stone is used, the Contractor shall haul away such surplus material.

A.29. Iron Bars

The Contractor is responsible for the cost of an Ontario Land Surveyor to replace any iron bars that are altered or destroyed during the course of the construction.

A.30. Rip-Rap



Rip-rap shall be quarry stone rip-rap material and shall be the sizes specified in the Special Provisions. Broken concrete shall not be used as rip-rap unless otherwise specified.

A.31. Clearing, Grubbing and Brushing

This specification applies to all brushing where no specific detail is provided on the drawings or in the Special Provisions.

The Contractor shall clear, brush and stump trees from within the working area that interfere with the installation of the drainage system.

All trees, limbs and brush less than 150mm in diameter shall be mulched. Trees greater than 150mm in diameter shall be cut and neatly stacked in piles designated by the Landowners.

A.32. Restoration of Lawns

This specification applies to all lawn restoration where no specific detail is provided on the drawings or in the Special Provisions and no allowance for damages has been provided under Section 30 of the Drainage Act RSO 1990 to the affected property.

The Contractor shall supply “high quality grass seed” and the seed shall be broadcast by means of an approved mechanical spreader. All areas on which seed is to be placed shall be loose at the time of broadcast to a depth of 25mm. Seed and fertilizer shall be spread in accordance with the supplier’s recommendations unless otherwise directed by the Engineer. Thereafter it will be the responsibility of the Landowner to maintain the area in a manner so as to promote growth

END OF DIVISION



DIVISION B

Specifications for Open Drains



CONTENTS

B.1.	ALIGNMENT	1
B.2.	PROFILE	1
B.3.	EXCAVATION	1
B.4.	EXCAVATED MATERIAL.....	1
B.5.	EXCAVATION AT EXISTING BRIDGE AND CULVERT SITES	2
B.6.	PIPE CULVERTS.....	2
B.7.	RIP-RAP PROTECTION FOR CULVERTS	2
B.8.	CLEARING, GRUBBING AND MULCHING	2
B.9.	TRIBUTARY TILE OUTLETS.....	3
B.10.	SEEDING	3
B.11.	HYDRO SEEDING.....	3
B.12.	HAND SEEDING	3
B.13.	COMPLETION	3



DIVISION B – SPECIFICATIONS FOR OPEN DRAINS

B.1. Alignment

The drain shall be constructed in a straight line and shall follow the course of the present drain or water run unless noted on the drawings. Where there are unnecessary bends or irregularities on the existing course of the drain, the Contractor shall contact the Engineer before commencing work to verify the manner in which such irregularities or bends may be removed from the drain. All curves shall be made with a minimum radius of fifteen (15) metres from the centre line of the drain.

B.2. Profile

The Profile Drawing shows the depth of cuts from the top of the bank to the final invert of the ditch in metres and decimals of a metre, and also the approximate depth of excavated material from the bottom of the existing ditch to the final invert of the ditch. These cuts are established for the convenience of the Contractor; however, bench marks (established along the course of the drain) will govern the final elevation of the drain. The location and elevation of the bench marks are given on the Profile Drawing. Accurate grade control must be maintained by the Contractor during ditch excavation.

B.3. Excavation

The bottom width and the side slopes of the ditch shall be those shown on the drawings. If the channel cross-section is not specified it shall be a one metre bottom width with 1.5(h):1(v) side slopes. At locations along the drain where the cross section dimensions change, there shall be a transitional length of not less than 10:1 (five metre length to 0.5 metre width differential). Where the width of the bottom of the existing ditch is sufficient to construct the design width, then construction shall proceed without disturbing the existing banks.

Where existing side slopes become unstable, the Contractor shall immediately notify the Engineer. Alternative methods of construction and/or methods of protection will then be determined prior to continuing work.

Where an existing drain is being relocated or where a new drain is being constructed, the Contractor shall strip the topsoil for the full width of the drain, including the location of the spoil pile. Upon completion of levelling, the topsoil shall be spread to an even depth across the full width of the spoil.

An approved hydraulic excavator shall be used to carry out the excavation of the open ditch unless otherwise directed by the Engineer.

B.4. Excavated Material

Excavated material shall be placed on the low side of the drain or opposite trees and fences. The Contractor shall contact all Landowners before proceeding with the work to verify the location to place and level the excavated material.

No excavated material shall be placed in tributary drains, depressions, or low areas which direct water behind the spoil bank. The excavated material shall be placed and levelled to a maximum depth of 200 mm, unless instructed otherwise and commence a minimum of one (1) metre from the top of the bank. The edge of the spoil bank away from the ditch shall be feathered down to the existing ground; the edge of the spoil bank nearest the ditch shall have a maximum slope of 2(h):1(v). The material shall be levelled such that it may be cultivated with ordinary farm equipment without causing undue



hardship to the farm machinery and farm personnel. No excavated material shall cover any logs, brush, etc. of any kind.

Any stones or boulders which exceed 300mm in diameter shall be removed and disposed of in a location specified by the Landowner.

Where it is necessary to straighten any unnecessary bends or irregularities in the alignment of the ditch or to relocate any portion or all of an existing ditch, the excavated material from the new cut shall be used for backfilling the original ditch. Regardless of the distance between the new ditch and the old ditch, no extra compensation will be allowed for this work and must be included in the Contractor's lump sum price for the open work.

B.5. Excavation at Existing Bridge and Culvert Sites

The Contractor shall excavate the drain to the full specified depth under all bridges and to the full width of the structure. Temporary bridges may be carefully removed and left on the bank of the drain but shall be replaced by the Contractor when the excavation is complete. Permanent bridges must, if at all possible, be left intact. All necessary care and precautions shall be taken to protect the structure. The Contractor shall notify the Landowner if excavation will expose the footings or otherwise compromise the structural integrity of the structure.

The Contractor shall clean through all pipe culverts to the grade and width specified on the profile.

B.6. Pipe Culverts

All pipe culverts shall be installed in accordance with the standard detail drawings. If couplers are required, five corrugation couplers shall be used for up to and including 1200mm diameter pipes and 10 corrugation couplers for greater than 1200mm diameter pipes.

When an existing crossing is being replaced, the Contractor may backfill the new culvert with the existing native material that is free of large rocks and stones. The Contractor is responsible for any damage to a culvert pipe that is a result of rocks or stones in the backfill.

B.7. Rip-Rap Protection For Culverts

Quarry stone rip-rap shall be used as end treatment for new culverts and placed on geotextile filter material (Mirafi 160N or approved equal). The rip-rap shall be adequately keyed in along the bottom of the slope, and shall extend to the top of the pipe or as directed on the drawings. The maximum slope for rip-rap shall be 1(h):1(v) or as directed by the Engineer.

The Contractor shall be responsible for any defects or damages that may develop in the rip-rap or the earth behind the rip-rap that the Engineer deems to have been fully or partially caused by faulty workmanship or materials.

B.8. Clearing, Grubbing and Mulching

Prior to excavation, all trees, scrub, fallen timber and debris shall be removed from the side slopes of the ditch and for such a distance on the working side so as to eliminate any interference with the construction of the drain or the spreading of the spoil. The side slopes shall be neatly cut and cleared flush with the slope whether or not they are affected directly by the excavation. With the exception of large stumps causing damage to the drain, the side slopes shall not be grubbed. All other cleared areas shall be grubbed and the stumps put into piles for disposal by the Landowner.



All trees or limbs 150mm or larger, that is necessary to remove, shall be cut, trimmed and neatly stacked in the working width for the use or disposal by the Landowner. Brush and limbs less than 150mm in diameter shall be mulched. Clearing, grubbing and mulching shall be carried out as a separate operation from the excavation of the ditch, and shall not be completed simultaneously at the same location.

B.9. Tributary Tile Outlets

All tile outlets in existing ditches shall be marked by the Landowner prior to excavation. The Contractor shall guard against damaging the outlets of tributary drains. Any tile drain outlets that were marked or noted on the drawings and are subsequently damaged by the Contractor shall be repaired by the Contractor at his expense. The Landowner shall be responsible for repairs to damaged tile outlets that were not marked.

B.10. Seeding

The side slopes where disturbed shall be seeded using an approved grass seed mixture. The grass seed shall be applied the same day as the excavation of the open ditch.

Grass seed shall be fresh, clean and new crop seed, meeting the requirements of the MTO and composed of the following varieties mixed in the proportion by weight as follows:

- 55% Creeping Red Fescue
- 40% Perennial Rye Grass
- 5% White Clover

Grass seed shall be applied at the rate of 100 kg/ha.

B.11. Hydro Seeding

The areas specified in the contract document shall be hydro seeded and mulched upon completion of construction in accordance with O.P.S.S. 572.

B.12. Hand Seeding

Placement of the seed shall be of means of an approved mechanical spreader.

B.13. Completion

At the time of completion and final inspection, all work in the Contract shall have the full dimensions and cross-sections specified without any allowance for caving of banks or sediment in the ditch bottom.

END OF DIVISION



SPECIAL PROVISIONS

Shafley Municipal Drain



CONTENTS

1.0	GENERAL	1
2.0	UTILITIES	1
3.0	WORKING AREA AND ACCESS	1
4.0	CLEARING BRUSHING AND MULCHING	2
5.0	OPEN DITCH EXCAVATION	2
6.0	EXCAVATED MATERIAL	2
7.0	SEEDING	2
8.0	CULVERT INSTALLATIONS	2
9.0	BANK REPAIR	2
10.0	ROAD CROSSINGS	3
11.0	RIP-RAP	3
12.0	EROSION AND SEDIMENT CONTROL	3



Special Provisions means special directions containing requirements particular to the work not adequately provided for by the standard or supplemental specifications. Special provisions shall take precedence and govern over any standard or supplemental specification.

1.0 GENERAL

The Contractor shall notify the Landowner, the Drainage Superintendent, and the Engineer 48 hours prior to construction.

The Contractor shall arrange a pre-construction meeting and shall invite the Landowners on whose property work will take place, and the Engineer, and the Drainage Superintendent.

The Contractor shall verify the location of the new drainage system with the Engineer and Landowner prior to construction.

The Contractor shall check and verify all dimensions and elevations and report any discrepancies to the Engineer prior to proceeding with the work.

The Contractor shall be responsible for settlement within the warranty period.

2.0 UTILITIES

All utilities shall be located and uncovered in the affected areas by the Contractor prior to construction.

The locations and elevations of all utilities shown on the drawings are approximate locations. Actual locations and elevations of all utilities must be verified by the Contractor prior to construction.

The Contractor shall arrange to have a representative of the utility owner on site during construction if it is a requirement by the utility owner.

3.0 WORKING AREA AND ACCESS

Access to the working area shall be designated by the Landowner.

The working area shall be in accordance with the following average widths.

Drain Segment and Station Range	Property Roll No.	Working side	Average Working Width for Construction	Average Working Width for Future Maintenance
0+020 to 1+048	12-179, 12-079-01, 12-178	West	12m	10m
1+062 to 1+495	12-177	East	12m	10m
1+523 to 1+730	12-176	East	12m	10m
1+730 to 1+922	Smith Road	West	6m	6m
1+937 to 2+162	12-179-15, 12-180-01	West	12m	10m



2+162 to 2+202	Smith Road	East	6m	6m
2+202 to 2+959	12-180	West	12m	10m
2+973 to 3+095	12-172	East	12m	10m

4.0 CLEARING BRUSHING AND MULCHING

The Contractor shall clear, brush and mulch trees from within the working area that interfere with the construction of the drainage system. The Contractor shall not clear all trees within the working area unless the full working width in a specific section is required for the installation of the drain and unless the Engineer has authorized the full clearing of the trees.

All trees, limbs, and brush less than 150mm in diameter shall be mulched/chipped. Clearing and brushing shall be done prior to the construction of the drain. Trees and branches greater than 150mm in diameter shall be cut into lengths no greater than four metres and placed in nearby stacks designated by the Landowner. Trees removed from road right-of-ways shall be mulched or disposed of offsite by the Contractor.

5.0 OPEN DITCH EXCAVATION

An approved hydraulic excavator shall be used to carry out the excavation of the open ditch. The open ditch shall have a 900mm bottom width and shall be parabolic in shape. The side slopes shall be a 1.5H:1V or flatter.

6.0 EXCAVATED MATERIAL

The excavated material from the ditch cleanout shall be hauled and used for the construction of the ditch enclosure on the Collver Municipal Drain.

7.0 SEEDING

The Contractor shall supply and hydroseed an approved seed mixture (OPS 803 – Lowland Mix), complete with a bonded fibre matrix mulch over the disturbed areas.

All seed shall be applied using the manufacturer's application recommendations.

8.0 CULVERT INSTALLATIONS

The Contractor shall install the culverts in accordance with the attached details.

9.0 BANK REPAIR

In areas where high levels of erosion have occurred, the Contractor shall reshape the banks to match typical bank side slopes. The Contractor shall then place geo-textile filter material and stone riprap for long term bank stabilization.



10.0 ROAD CROSSINGS

10.1 Notice

The Contractor shall notify the Engineer and the Township of Wainfleet a minimum of 48 hours prior to the scheduled road crossing.

The Contractor shall notify all emergency services and local district school boards of the road enclosure.

Detour routes and plans shall be provided to all relevant local authorities in accordance with their respective notification protocols.

10.2 Traffic Control

The Contractor shall be responsible to arrange all traffic control signals, signs and devices that are required for safe and proper traffic management during the installation of the drainage system. The Contractor shall contact Huron County for specific local procedures, guidelines, and timelines. Traffic control shall meet the standards of Book 7 of the Ontario Traffic Manual.

10.3 Road Restoration

The Contractor shall remove and dispose of offsite, all excavated material unsuitable for use as backfill.

The Contractor shall grade the road ditches to the ditch. Any areas disturbed within the Road Right-of-Way shall be topsoiled and hydroseeded with an approved grass seed mixture (OPS 803 – Standard Roadside Mix).

11.0 RIP-RAP

All stone rip-rap material shall be quarry stone 150mm to 300mm diameter and placed to a depth of 300mm, unless otherwise noted. All rip-rap material shall be placed on geo-textile filter material.

12.0 EROSION AND SEDIMENT CONTROL

The Contractor shall provide adequate erosion and sediment control for the duration of construction including monitoring and maintenance of the control measures put in place. The Contractor shall inspect the erosion and sediment control measures regularly, and specifically before predicted rainfall events, and after rainfall events.

SHAFLEY MUNICIPAL DRAIN

Watershed Plan

NOTES:

- THIS MAP WAS CREATED USING NIAGARA REGION GEOGRAPHIC INFORMATION SYSTEM DIGITAL DATA. THIS MAP IS A SECONDARY PRODUCT WHICH HAS NOT BEEN VERIFIED BY NIAGARA REGION.
- THE CONTOURS WERE CREATED USING IMAGERY DERIVED DIGITAL DATA (2015) FROM LAND INFORMATION ONTARIO.

BENCHMARK DESCRIPTIONS

- BENCHMARK No. 1** ELEV.=175.38
TOP CENTER UPSTREAM END OF CSPA CULVERT 8m EAST OF STA. 0+000 (MAIN)
- BENCHMARK No. 2** ELEV.=175.93
TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 0+615 (MAIN)
- BENCHMARK No. 3** ELEV.=177.96
NAIL IN WEST FACE OF 1200mmØ TREE 15m EAST OF STA. 0+832 (MAIN)
- BENCHMARK No. 4** ELEV.=176.33
TOP CENTER DOWNSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+497 (MAIN)
- BENCHMARK No. 5** ELEV.=176.26
TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+518 (MAIN)
- BENCHMARK No. 6** ELEV.=176.65
TOP CENTER UPSTREAM END OF 750mmØ CSP CULVERT AT STA. 2+194 (MAIN)

LEGEND


- LOT/CONCESSION LINE
- PROPERTY LINE
- MAJOR WATERSHED BOUNDARY
- MINOR WATERSHED BOUNDARY
- WETLAND LIMIT
- BENCHMARK LOCATION
- B.M. 1 (123.45) BENCHMARK No.
- B.M. 1 (123.45) BENCHMARK ELEVATION
- JOHN & JANE SMITH (12-345) LANDOWNER NAME(S)
- JOHN & JANE SMITH (12-345) ASSESSMENT ROLL No. (ABBREVIATED)
- JOHN & JANE SMITH (12-345) AREA WITHIN WATERSHED

- EXISTING FEATURES:**
- DRAIN NAME** OPEN DRAIN WITH CROSSING AND FLOW DIRECTION
 - DRAIN NAME** CLOSED DRAIN WITH CATCH BASIN, MANHOLE AND FLOW DIRECTION
 - OVERLAND FLOW PATH
- PROPOSED FEATURES:**
- DRAIN NAME** OPEN DRAIN WITH CROSSING AND FLOW DIRECTION

6	REPORT SUBMISSION	25-12-18
5	PUBLIC INFORMATION MEETING	25-07-09
4	PETITIONER MEETING	25-01-09
3	CP RAILWAY SUBMISSION	23-05-31
2	PETITIONER MEETING	22-10-19
1	ON-SITE MEETING	19-11-20
No.	REVISION	DATE (YY-MM-DD)




DRAWN BY: R.U.	DESIGNED BY: A.H.	CHECKED BY: S.B.	DRAWING 1 OF 7
DATE: 2025-12-18		REFERENCE No. WNFLT-002	



SCHEDULE OF OWNERSHIP

ST. No.	OWNERSHIP	ROLL NO.	WATERSHED AREA
SMITH ROAD			
63687	RACHEL VANHEEL	12-172-02	0.4 HA.
63645	JAMES & ENGKINA VANAMERONGEN	12-173-50	1.3 HA.
63644	RICHARD & LAURA GERRYTS	12-179	0.7 HA.
63643	KEVIN & TACEY VIS	12-175	0.3 HA.
63641	AKBAR AMANALI & NADIA MERCHANT	12-174	0.7 HA.
63634	NICHOLAS MASI & ANN STEPHANIE	12-179-05	1.4 HA.



SHAFLEY MUNICIPAL DRAIN

Main Drain (Open) Profile
(Sta. 0+000 to Sta. 1+523)

CULVERT DETAILS
D/S INV. = 173.12
U/S INV. = 173.50
GRADE = 1.43%
LENGTH = 26m
DIAMETER = 1200mm


CULVERT DETAILS
D/S INV. = 173.92
U/S INV. = 173.99
GRADE = 0.15%
LENGTH = 45m
DIAMETER = 1200mm

CULVERT DETAILS
D/S INV. = 174.33
U/S INV. = 174.36
GRADE = 0.07%
LENGTH = 45m
DIAMETER = 1600mm

CULVERT DETAILS
D/S INV. = 174.63
U/S INV. = 174.65
GRADE = 0.07%
LENGTH = 18m
DIAMETER = 1600mm

CULVERT DETAILS
D/S INV. = 174.66
U/S INV. = 174.67
GRADE = 0.07%
LENGTH = 18m
DIAMETER = 1600mm


CULVERT DETAILS
D/S INV. = 174.99
U/S INV. = 175.00
GRADE = 0.05%
LENGTH = 22m
DIAMETER = 1600mm



BENCHMARK DESCRIPTIONS

BENCHMARK No. 1	ELEV.=175.38
TOP CENTER UPSTREAM END OF CSPA CULVERT 8m EAST OF STA. 0+000 (MAIN)	
BENCHMARK No. 2	ELEV.=175.93
TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 0+615 (MAIN)	
BENCHMARK No. 3	ELEV.=177.96
NAIL IN WEST FACE OF 1200mmØ TREE 15m EAST OF STA. 0+832 (MAIN)	
BENCHMARK No. 4	ELEV.=176.33
TOP CENTER DOWNSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+497 (MAIN)	
BENCHMARK No. 5	ELEV.=176.26
TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+518 (MAIN)	
BENCHMARK No. 6	ELEV.=176.65
TOP CENTER UPSTREAM END OF 750mmØ CSP CULVERT AT STA. 2+194 (MAIN)	

PROFILE SCALES




6	REPORT SUBMISSION	25-12-18
5	PUBLIC INFORMATION MEETING	25-07-09
4	PETITIONER MEETING	25-01-09
3	CP RAILWAY SUBMISSION	23-05-31
2	PETITIONER MEETING	22-10-19
1	ON-SITE MEETING	19-11-20
No.	REVISION	DATE (YY-MM-DD)



DRAWN BY: R.U.	DESIGNED BY: A.H.	CHECKED BY: S.B.	DRAWING 2 OF 7
DATE: 2025-12-18		REFERENCE No. WNFLT-002	

SHAFLEY MUNICIPAL DRAIN

Main Drain (Open) Profile
(Sta. 1+523 to Sta. 3+098)





BENCHMARK DESCRIPTIONS

BENCHMARK No. 1	ELEV.=175.38
TOP CENTER UPSTREAM END OF CSPA CULVERT 8m EAST OF STA. 0+000 (MAIN)	
BENCHMARK No. 2	ELEV.=175.93
TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 0+615 (MAIN)	
BENCHMARK No. 3	ELEV.=177.96
NAIL IN WEST FACE OF 1200mmØ TREE 15m EAST OF STA. 0+832 (MAIN)	
BENCHMARK No. 4	ELEV.=176.33
TOP CENTER DOWNSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+497 (MAIN)	
BENCHMARK No. 5	ELEV.=176.26
TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+518 (MAIN)	
BENCHMARK No. 6	ELEV.=176.65
TOP CENTER UPSTREAM END OF 750mmØ CSP CULVERT AT STA. 2+194 (MAIN)	

NEIGHBOURING OWNERSHIP

172	DANIEL & MENNO VANDER MEER 12-176	AKBAR AMANALI & NADIA MERCHANT 12-174	KEVIN & TACEY VIS 12-175	HIHOJO LTD. 12-179-15	KATHLEEN PERRON 12-180-01	YVONNE HESSELS 12-180	VANDER MEER FARMS LTD. 12-172
171	JAMES & ENGEKINA VANAMERONGEN 12-173-50						
170	SMITH ROAD						



6	REPORT SUBMISSION	25-12-18
5	PUBLIC INFORMATION MEETING	25-07-09
4	PETITIONER MEETING	25-01-09
3	CP RAILWAY SUBMISSION	23-05-31
2	PETITIONER MEETING	22-10-19
1	ON-SITE MEETING	19-11-20
No.	REVISION	DATE (YY-MM-DD)
























DRAWN BY: R.U.	DESIGNED BY: A.H.	CHECKED BY: S.B.	DRAWING 3 OF 7
DATE: 2025-12-18		REFERENCE No. WNFLT-002	

SHAFLEY MUNICIPAL DRAIN

Sections - Main Drain (Open)
(Sta. 0+100 to Sta. 1+050)

BENCHMARK DESCRIPTIONS

BENCHMARK No. 1 TOP CENTER UPSTREAM END OF CSPA CULVERT 8m EAST OF STA. 0+000 (MAIN)	ELEV.=175.38
BENCHMARK No. 2 TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 0+615 (MAIN)	ELEV.=175.93
BENCHMARK No. 3 NAIL IN WEST FACE OF 1200mmØ TREE 15m EAST OF STA. 0+832 (MAIN)	ELEV.=177.96
BENCHMARK No. 4 TOP CENTER DOWNSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+497 (MAIN)	ELEV.=176.33
BENCHMARK No. 5 TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+518 (MAIN)	ELEV.=176.26
BENCHMARK No. 6 TOP CENTER UPSTREAM END OF 750mmØ CSP CULVERT AT STA. 2+194 (MAIN)	ELEV.=176.65



6	REPORT SUBMISSION	25-12-18
5	PUBLIC INFORMATION MEETING	25-07-09
4	PETITIONER MEETING	25-01-09
3	CP RAILWAY SUBMISSION	23-05-31
2	PETITIONER MEETING	22-10-19
1	ON-SITE MEETING	19-11-20
No.	REVISION	DATE (YY-MM-DD)
























DRAWN BY: R.U.	DESIGNED BY: A.H.	CHECKED BY: S.B.	DRAWING 4 OF 7
DATE: 2025-12-18		REFERENCE No. WNFLT-002	

SHAFLEY MUNICIPAL DRAIN

Sections - Main Drain (Open)
(Sta. 1+100 to Sta. 2+050)

BENCHMARK DESCRIPTIONS

- BENCHMARK No. 1** ELEV.=175.38
TOP CENTER UPSTREAM END OF CSPA CULVERT 8m EAST OF STA. 0+000 (MAIN)
- BENCHMARK No. 2** ELEV.=175.93
TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 0+615 (MAIN)
- BENCHMARK No. 3** ELEV.=177.96
NAIL IN WEST FACE OF 1200mmØ TREE 15m EAST OF STA. 0+832 (MAIN)
- BENCHMARK No. 4** ELEV.=176.33
TOP CENTER DOWNSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+497 (MAIN)
- BENCHMARK No. 5** ELEV.=176.26
TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+518 (MAIN)
- BENCHMARK No. 6** ELEV.=176.65
TOP CENTER UPSTREAM END OF 750mmØ CSP CULVERT AT STA. 2+194 (MAIN)



6	REPORT SUBMISSION	25-12-18
5	PUBLIC INFORMATION MEETING	25-07-09
4	PETITIONER MEETING	25-01-09
3	CP RAILWAY SUBMISSION	23-05-31
2	PETITIONER MEETING	22-10-19
1	ON-SITE MEETING	19-11-20
No.	REVISION	DATE (YY-MM-DD)
























DRAWN BY: R.U.	DESIGNED BY: A.H.	CHECKED BY: S.B.	DRAWING 5 OF 7
DATE: 2025-12-18		REFERENCE No. WNFLT-002	

SHAFLEY MUNICIPAL DRAIN

Sections - Main Drain (Open)
(Sta. 2+100 to Sta. 3+050)

BENCHMARK DESCRIPTIONS

BENCHMARK No. 1 TOP CENTER UPSTREAM END OF CSPA CULVERT 8m EAST OF STA. 0+000 (MAIN)	ELEV.=175.38
BENCHMARK No. 2 TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 0+615 (MAIN)	ELEV.=175.93
BENCHMARK No. 3 NAIL IN WEST FACE OF 1200mmØ TREE 15m EAST OF STA. 0+832 (MAIN)	ELEV.=177.96
BENCHMARK No. 4 TOP CENTER DOWNSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+497 (MAIN)	ELEV.=176.33
BENCHMARK No. 5 TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+518 (MAIN)	ELEV.=176.26
BENCHMARK No. 6 TOP CENTER UPSTREAM END OF 750mmØ CSP CULVERT AT STA. 2+194 (MAIN)	ELEV.=176.65



6	REPORT SUBMISSION	25-12-18
5	PUBLIC INFORMATION MEETING	25-07-09
4	PETITIONER MEETING	25-01-09
3	CP RAILWAY SUBMISSION	23-05-31
2	PETITIONER MEETING	22-10-19
1	ON-SITE MEETING	19-11-20
No.	REVISION	DATE (YY-MM-DD)







DRAWN BY: R.U.	DESIGNED BY: A.H.	CHECKED BY: S.B.	DRAWING 6 OF 7
DATE: 2025-12-18		REFERENCE No. WNFLT-002	

SHAFLEY MUNICIPAL DRAIN

Details

BENCHMARK DESCRIPTIONS

BENCHMARK No. 1 TOP CENTER UPSTREAM END OF CSPA CULVERT 8m EAST OF STA. 0+000 (MAIN)	ELEV.=175.38
BENCHMARK No. 2 TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 0+615 (MAIN)	ELEV.=175.93
BENCHMARK No. 3 NAIL IN WEST FACE OF 1200mmØ TREE 15m EAST OF STA. 0+832 (MAIN)	ELEV.=177.96
BENCHMARK No. 4 TOP CENTER DOWNSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+497 (MAIN)	ELEV.=176.33
BENCHMARK No. 5 TOP CENTER UPSTREAM END OF 1200mmØ CSP CULVERT AT STA. 1+518 (MAIN)	ELEV.=176.26
BENCHMARK No. 6 TOP CENTER UPSTREAM END OF 750mmØ CSP CULVERT AT STA. 2+194 (MAIN)	ELEV.=176.65




PROPOSED CULVERTS

STATION	DIAMETER	LENGTH	INVERT	STREAMBED	CORRUGATIONS	THICKNESS
1+930	1200mm	16m	U.S.E. = 175.22 D.S.E. = 175.21	U.S.E. = 175.42 D.S.E. = 175.41	125mm X 25mm	2.80mm
2+967	900mm	14m	U.S.E. = 175.95 D.S.E. = 175.94	U.S.E. = 176.10 D.S.E. = 176.09	68mm X 13mm	2.00mm

SUGGESTED FUTURE CULVERTS

STATION	DIAMETER	LENGTH	INVERT	STREAMBED	CORRUGATIONS	THICKNESS
1+024	1600mm	18m	U.S.E. = 174.65 D.S.E. = 174.63	U.S.E. = 174.85 D.S.E. = 174.83	125mm X 25mm	2.80mm
1+053	1600mm	18m	U.S.E. = 174.67 D.S.E. = 174.66	U.S.E. = 174.87 D.S.E. = 174.86	125mm X 25mm	2.80mm
1+505	1600mm	22m	U.S.E. = 175.00 D.S.E. = 174.99	U.S.E. = 175.20 D.S.E. = 175.19	125mm X 25mm	2.80mm




PROPOSED CULVERTS

STATION	DIAMETER	LENGTH	INVERT	STREAMBED	CORRUGATIONS	THICKNESS
0+015	1200mm	26m	U.S.E. = 173.50 D.S.E. = 173.12	U.S.E. = 174.70 D.S.E. = 174.32	125mm X 25mm	2.80mm
0+074	1200mm	45m	U.S.E. = 173.99 D.S.E. = 173.92	U.S.E. = 174.19 D.S.E. = 174.16	125mm X 25mm	2.80mm
0+606	1600mm	45m	U.S.E. = 174.36 D.S.E. = 174.33	U.S.E. = 174.56 D.S.E. = 174.53	125mm X 25mm	2.80mm
2+189	900mm	12m	U.S.E. = 175.36 D.S.E. = 175.35	U.S.E. = 175.56 D.S.E. = 175.55	68mm X 13mm	2.00mm
2+460	900mm	12m	U.S.E. = 175.51 D.S.E. = 175.50	U.S.E. = 175.71 D.S.E. = 175.70	68mm X 13mm	2.00mm

SUGGESTED FUTURE CULVERTS

STATION	DIAMETER	LENGTH	INVERT	STREAMBED	CORRUGATIONS	THICKNESS
1+736	1200mm	12m	U.S.E. = 175.12 D.S.E. = 175.11	U.S.E. = 175.32 D.S.E. = 175.31	125mm X 25mm	2.80mm
1+836	1200mm	12m	U.S.E. = 175.17 D.S.E. = 175.16	U.S.E. = 175.37 D.S.E. = 175.36	125mm X 25mm	2.80mm
1+867	1200mm	12m	U.S.E. = 175.19 D.S.E. = 175.18	U.S.E. = 175.39 D.S.E. = 175.38	125mm X 25mm	2.80mm

TYPICAL ASPHALT ROAD CULVERT DETAIL
N.T.S.



6	REPORT SUBMISSION	25-12-18
5	PUBLIC INFORMATION MEETING	25-07-09
4	PETITIONER MEETING	25-01-09
3	CP RAILWAY SUBMISSION	23-05-31
2	PETITIONER MEETING	22-10-19
1	ON-SITE MEETING	19-11-20
No.	REVISION	DATE (YY-MM-DD)



DRAWN BY: R.U.	DESIGNED BY: A.H.	CHECKED BY: S.B.	DRAWING 7 OF 7
DATE: 2025-12-18		REFERENCE No. WNFLT-002	